


# LHC Commissioning with Beam Overall Strategy

**Mike Lamont**  
**AB-OP**


**6<sup>th</sup> April 2005**

# T18

- Beam down – first shot. →
- Full set of measurements ↓
  - optics, aperture etc.



Lionel Mestre



## What does this tell us?

# LHC Beam Commissioning

- **OBJECTIVES**
- **PREPARATION**
- **PLANNING**
  
- **KEEP IT SIMPLE**
- **STAGE IT**
- **KEEP IT SAFE**

# Objectives

## Commissioning the LHC with beam - Stage One

- Establish colliding beams as quickly as possible
- Safely
- Without compromising further progress

**Take two moderate intensity multi-bunch beams to high energy and collide them.**

# More Specifically

43 on 43 with 3 to 4 x 10<sup>10</sup> ppb to 7 TeV

- **No parasitic encounters**
  - No crossing angle
  - No long range beam
  - Larger aperture
- **Instrumentation**
- **Good beam for RF, Vacuum...**
- **Lower energy densities**
  - Reduced demands on beam dump system
  - Collimation
  - Machine protection
- **Luminosity**
  - 10<sup>30</sup> cm<sup>-2</sup>s<sup>-1</sup> at 18 m
  - 2 x 10<sup>31</sup> cm<sup>-2</sup>s<sup>-1</sup> at 1 m

# and in the process

- **Commission**
  - the Equipment
  - the Instrumentation
  - the Machine protection system

**to the levels required.**


**Looking for an efficient commissioning path to  
get us to the above objectives**

**Stage two definition to follow**

# Preparation

**Clear aim to commission/fix/test  
everything that can be:  
before beam.**

# LHC - 2007



**EXIT HWC**

**EXIT CHECKOUT**

**EXIT TI8/TI2**

# Exit HWC - 1

Given installation, technical infrastructure etc. etc.

- **Implicitly:**

- Beam Vacuum [warm & cold]
- Cooling and Ventilation
- Cryogenics Plant
- Cryostat Instrumentation
- Electrical Network
- Insulation Vacuum
- Powering Interlock
- QRL Instrumentation
- QRL Vacuum
- Radiation Monitors
- Software Interlock System
- Access
- Survey/Alignment

**MOVE FROM HWC MODE  
TO OPERATION MODE**



- **Monitoring, logging, display, PM, Diagnostics**
- **Control applications**
- **Coupling between systems**
- **Recovery procedures** from CCR clearly defined etc. etc.

# Exit HWC - II

- All magnet circuits [warm & cold]
- Power converters
- Kickers, Septa
- Collimators, Absorbers
- Beam dumps
- RF
  - Power systems, low level, cavities, TFB
- Instrumentation
- Machine protection
  - QPS, Energy Extraction, Power Interlock Controllers
- Controls

# Machine checkout

- **By Operations**
- **With support of equipment specialists, HWC team etc.**
- **From the PCR**

**Drive all relevant systems in a synchronized way through the complete operational sequence**

**This where operations get serious**



# Exit machine checkout - 1

- **RF**
  - Pre-pulses, low level control [cavity control, synchro, beam control, longitudinal damper], transverse damper, power systems. Diagnostics.
  - Synchronisation with injectors
- **Power converters**
  - tracking
  - control, ramping, squeezing, real-time
- **Kickers, septa,**
- **Collimators, absorbers**
- **Dump:**
  - timing, post-mortem, inject and dump
- **Beam Instrumentation**
  - pre-commission, timing, acquisition tests, interface to control system

# Exit Machine Checkout - 2

- **Interlocks & Machine Protection**
  - Equipment interfaces, links, logic, controls,
  - PIC, WIC, BIC, Safe Beam Flags
  - Software interlocks
  - QPS, Energy extraction
    - displays, diagnostics, post-mortem, recovery
  - Energy meter

# Exit Machine Checkout - 3

- **Controls:**

- **Slow timing, fast timing, synchronisation**
- **Alarms, logging, post mortem, fixed displays**
- **Equipment control & access**
- **Analogue acquisition**
- **Software: measurements, trajectory acquisition and correction, ramping etc. etc.**
- **Controls infrastructure: servers, databases etc.**
- **Sequencer, injection management**
- **Procedures for sliding bumps etc. etc.**

# Exit Machine Checkout - 4

- **Settings etc.**
  - calibrations, optics, transfer functions, ramp, squeeze...
- **Radiation monitoring**
- **Access system**
  - INB, EIS
  - Operation
- **Experiments**
  - Data interchange
  - Beam aborts

# Exit injectors and transfer lines

- **SPS LHC cycle**
  - All requisite beams available
  - Beam quality
  - Delivered when required
  
- **TI8 & TI2**
  - Fully qualified LHC pilot beams to final TED

# Pre-beam: Magnets

- **Errors: all circuits, full cycle**
  - geometric, beam screen, saturation
  - eddy,
  - RMS/Persistent currents
    - static model
    - powering history dependent model
    - on-line reference magnets
- **Cycle path – all magnets**
- **Transfer functions**
  - for all magnet circuits
  - hysteresis behaviour for corrector circuits where appropriate
- **Strategy for:**
  - excitation of nested correctors
  - cycling nested pc/magnets

```
b1pM_MBRS := 0.0000;  
b1gM_MBRS := 0.0000;  
b2pM_MBRS := -0.1088;  
b2gM_MBRS := 0.1904;  
b3pM_MBRS := -4.1431;  
b3gM_MBRS := -2.1825;
```





Figure 3 : Field strength of **MCS** corrector : difference between the strength and straight line giving the average to enlighten the hysteresis due to persistent currents.

# Planning: with beam

<b>1</b>	<b>Injection</b>
<b>2</b>	<b>First turn</b>
<b>3</b>	<b>Circulating beam</b>
<b>4</b>	<b>450 GeV: initial commissioning</b>
<b>5</b>	<b>450 GeV: detailed measurements</b>
<b>6</b>	<b>450 GeV: 2 beams</b>
<b>7</b>	<b>Nominal cycle</b>
<b>8</b>	<b>Snapback – single beam</b>
<b>9</b>	<b>Ramp – single beam</b>
<b>10</b>	<b>Single beam to physics energy</b>
<b>11</b>	<b>Two beams to physics energy</b>
<b>12</b>	<b>Physics</b>
<b>13</b>	<b>Commission squeeze</b>
<b>14</b>	<b>Physics partially squeezed</b>

# Beam

- **Pilot Beam:**
  - Single bunch, 5 to 10 x 10<sup>9</sup> protons
  - Possibly reduced emittance
- **Intermediate single:**
  - 3 to 4 x 10<sup>10</sup> ppb
- **4 bunches etc. pushing towards...**
- **43 bunches**
  - 3 to 4 x 10<sup>10</sup> ppb

Will stepping up & down  
in intensity/number of  
bunches through the  
phases

## First turn

- Commission injection region
- Instrumentation
- Threading

PILOT

RING 1  
RING2

## Establish circulating beam

- Circulating low intensity beam

PILOT

RING 1  
RING2

## 450 GeV Initial

- Polarities and aperture checked.
- Basic optics checks performed.
- First pass commissioning of BI performed.
- Phase 1 of machine protection system commissioning performed. .
- Beam Dump commissioned with beam

SINGLE  
INTERMEDIATE

RING 1  
RING2

## 450 GeV Detailed

- Well-adjusted beam parameters, detailed optics checks
- Fully functioning beam instrumentation.
- Machine protection as required for ramp
- RF - beam control loops operational and adjusted

SINGLE  
INTERMEDIATE  
++

RING 1  
RING2

## Two beam operation

- 2 beams, well-adjusted beam parameters,
- beam instrumentation, cross talk etc.

## Switch to nominal

- 2 beams, well-adjusted beam parameters,
- beam instrumentation, cross talk etc.

## Snapback

- Single beam, good transmission through snapback
- Requisite measurements (orbit, tune, chromaticity)

PILOT++

RING 1  
RING2




## Ramp Single Beam

- Single beam, good transmission to top energy
- **Commission beam dump in ramp**
- Stops in ramp - measurements
- RF

PILOT++

RING 1  
RING2



## Two beams to top energy

- Two beams, good transmission to top energy
- Measurements

43 x 43

COLLIDE




## Squeeze

- Single beam - step through squeeze
- Parameter control, measurements

SINGLE  
INTERMEDIATE

RING 1  
RING2




# At each phase:

- **Equipment commissioning with beam**
- **Instrumentation commissioning**
- **Checks with beam**
  - **BPM Polarity, corrector polarity, BPM response**
- **Machine protection**
- **Beam measurements**
  - **beam parameter adjustment, energy, linear optics checks, aperture etc. etc.**

# Transfer & Injection

LEFT OF IP2 (H plane)



- Objectives & **importance of preparation [hammered]**
- System Commissioning:
  - Hardware
  - **Machine Protection**
  - Beam Instrumentation
  - Controls



Procedure for  
commissioning with  
beam  
plus time estimate

# Transfer & Injection: Issues



- **Scheduling of T12 and IR2**
- **Keep T18 operational**
- **Sector test clearly a big advantage**
  
- **Machine Protection [general]**
  - Including full specification & formal acceptance
  - Imperative that we have a well-defined plan of how to commission the machine protection system with beam.
  - Providing an appropriate level of protection at each commissioning stage.

# 450 GeV: Initial

Commissioning tunes

Simple machine

De-Gauss cycle



- **Threading, First turn, circulating beam, RF capture**
- **Beam instrumentation:**
  - BPM, BCT, Screens, Tune
- **Beam parameter adjustment**
- **First pass optics and aperture measurements**
- **Equipment:**
  - RF, Beam Dump

# 450 GeV: consolidation

- **Measurements:**
  - Linear optics checks and correction
  - Beta beating, Emittance
  - Non-linear optics, higher orders
- **Equipment**
  - Collimators
  - RF, LFB, TFB
- **Instrumentation**
  - BLMs...
- **Machine Protection system**




**Well adjusted 450 GeV machine.**


**Machine Protection systems fully tested, approved  
and operational to take beam into the ramp**

# De-Gauss versus Nominal

1. Nominal cycle and wait 30 minutes
2. De-Gauss cycle






- **Zeros persistent current effects**
- **Stable in time**
- **No dependency on the powering history of the magnets**
- **Get a handle on persistent current amplitudes**
- **No 30 minutes wait**
- **HOWEVER:**
  - **Spend time commissioning a cycle we can't use operationally; plus possibly some beam dynamics issues**



# Ramp

- **Procedure detailed:**
  - Baseline Ramp
  - Power converters,
    - Pre-loaded functions, Real-time
  - RF
  - Dump
  - Timing
  - Stop in Ramp & Squeeze
- **Prerequisites include:**
  - Beam Instrumentation
    - Tune measurement
    - Q' measurement
    - Orbit
  - RMS:
    - predictions of snapback, transfer functions, static errors...
  - Machine Protection





During commissioning:

- **PC Tracking Studies**
- **Beam Dump Commissioning**
- **BLM threshold adjustment**

# Squeeze

- **Key Requirements**


- Separation
- Aperture
- Smooth powering
- Avoid low gradients and zero crossings

- **Tight Tolerances**

- Interplay between gradient errors and limits on tune, beta beating, dispersion, orbit
- Excellent control required: feedback desirable

- **Time**

- Given by power converter ramp rates
- 8.5 minutes per IP
- plus round off & collimator adjustments



Procedure detailed:




- **Collimators**
- **Power converters**
- **Monitoring**
- **Parameter control**

# Squeeze

- **Commissioning procedure:**
  - Squeeze one IP at a time without crossing angle
  - One IP at a time with crossing angle
  - Minimise intermediate solutions. **How many matched intermediate steps are required?**
  - Parallel squeeze in more than one IP
  
- **Issues**
  - Triplet correction for  $b^*$   0.7 m.
  - Transfer functions and triplet alignment  $\otimes$  errors
  - Reproducibility of transfer functions at low powering
  - Alignment optics



# Critical systems @ Start-up

- **BPMs**
  - Day 0: Orbit on pilot – immediate, turn by turn with BST
  - Systematic check for polarity errors etc.
  - System performance – long term
- **BLMs**
  - Day 0: “slow” monitors – immediate
  - BST for fast loss monitors
  - Calibration, Cross talk...
  - **Thresholds** - considerable effort
- **BCT**
  - Day 0: DC immediate, bunch to bunch – BST
  - Lifetime calculation – slow!
- **Tune**
  - Tune Day 0: Kick/FFT & multi- FFT
  - PLL – few weeks



# Critical systems @ Start-up

- **Chromaticity**
  - Day 0: Kick/Head-tail (BST)
  - Day 0: DQ v Df
  - Periodic momentum modulation – PLL
- **Coupling**
  - Day 0: Kick/Beam response
  - PLL: closest tune approach




**Clear need to get PLL (& BST) working ASAP**

**Good to see that the basics will be there from the start**

**Plus: SLM, LDM, AGM, RGM, Wire scanners, luminosity monitors.**

# Machine protection



**Need a well defined plan for the commissioning and integration of the Machine Protection System**



# How long?

	Phase	R1/2	Time [days]	
	Injection	2	1	2
1	First turn	2	3	6
2	Circulating beam	2	3	6
3	450 GeV: initial commissioning	2	4	8
4	450 GeV: detailed measurements	2	4	8
5	450 GeV: 2 beams	1	2	2
6	Nominal cycle	1	5	5
7	Snapback – single beam	2	3	6
8	Ramp – single beam	2	4	8
9	Single beam to physics energy	2	2	4
10	Two beams to physics energy	1	3	3
11	Physics	1	2	2
12	Commission squeeze	2	4	4
13	Physics partially squeezed	1		
	<b>TOTAL TIME (WITH BEAM)</b>			<b>60</b>

# Parallelism?

- **System tests with HWC ongoing**
  - Machine protection
  - Controls
  - RF/Injection/Collimators etc.
- **Machine checkout with HWC ongoing**
  - Sign over completed sectors to OP
- **TI2 commissioning – LHC with beam 2**
- **HWC – partial LHC with beam 2**
  - Implications: dump, radiation protection, access, resources, support etc.
- **LHC - partial beam 1 with beam 2**

**Options need examining**

# Conclusions

- **PREPARATION**
- **STAGING**
  - 43 x 43 colliding (in 3 months absolute minimum)
- **PLANNING**
  - Before beam
  - Phases detailed – work in progress

- [//cern.ch/lhc-commissioning](http://cern.ch/lhc-commissioning)
- [//cern.ch/lhc-injection-test](http://cern.ch/lhc-injection-test)

