

LARP


Development of TQ models based on 4-layer coils

Paolo Ferracin

LARP Collaboration Meeting
Port Jefferson
April 6 - 8, 2005



Superconducting Magnet Group



LARP


Outline

- Goals
- Design study
 - Magnet parameters
- Development steps and schedule
- Conclusions



Superconducting Magnet Group

Paolo Ferracin




LARP

Goals


- Explore magnet design **limits** for an LHC luminosity upgrade
 - Gradient **300+** T/m (90 mm bore)
 - Peak field in the conductor **15+** T
 - Coil stresses **150+** MPa
 - Support **structure**






LARP

Four-layer design: magnet parameters




	Units	Inner	Outer
Strand diameter	mm	0.70	0.70
Cu/Sc		0.85	0.85
Cable width	mm	10.050	10.050
Cable thickness	mm	1.260	1.260
Keystone angle	deg	1.42	1.13
Insulation	mm	0.125	0.125
Turns		34	52
SC area	cm ²	28	43
J _c (12 T, 4.2 K)	A/mm ²	3000	3000
T _{op}	K		1.9
J _{cu} @ I _{ss}	A/mm ²	2190	2190
G _{ss}	T/m		307
I _{ss}	kA		10.5
B _{peak}	T	15.6	15.6






LARP

Two-layer designs: magnet parameters




	Units	Inner	Outer
Strand diameter	mm	0.70	0.70
Cu/Sc		0.85	0.85
Cable width	mm	10.050	10.050
Cable thickness	mm	1.260	1.260
Keystone angle	deg	1.42	1.13
Insulation	mm	0.125	0.125
Turns		34	52
SC area	cm ²	28	43
J _c (12 T, 4.2 K)	A/mm ²	3000	3000
T _{op}	K		1.9
G _{ss} (two layers)	T/m	257	187
I _{ss} (two layers)	kA	16.6	13.5
B _{peak} (two layers)	T	13.4	14.5






Four-layer design with grading: magnet parameters




	Units	Inner	Outer
Strand diameter	mm	0.80	0.65
Cu/Sc		0.85	1.30
Cable width	mm	10.050	10.050
Cable thickness	mm	1.440	1.170
Keystone angle	deg	1.60	1.08
Insulation	mm	0.125	0.125
Turns		35	40
SC area	cm ²	34	31
J_c (12 T, 4.2 K)	A/mm ²	3000	3000
T_{op}	K	1.9	
J_{cu} @ I_{ss}	A/mm ²	2090	2130
G_{ss} (four layers)	T/m	313	
I_{ss} (four layers)	kA	11.6	
B_{peak} (four layers)	T	15.9	13.6






Four-layer design: without and with grading

LARP




- Gradient: **307 T/m**
- Peak field: **15.6 T**
- SC area: **71 cm²**



- Gradient: **313 T/m**
- Peak field: **15.9 T**
- SC area: **65 cm²**





Development steps

LARP

1. TQ1b

- Design, fabrication, assembly, and test of **outer double-layer coil** (130 mm aperture)

2. TQ4L-1

- Assembly and test of **TQ1b** coil and **TQ1a** coil


3. TQ1c

- Design, fabrication, assembly, and test of **new inner double-layer coil**

4. TQ4L-2

- Assembly and test of **TQ1c** coil and **TQ1b** coil





LARP

Step 1: TQ1b


TQ1b (outer double-layer)	FTE		Labor	M&S	M&S+G&A	Total
	P/E	D/T				
Design & Analysis						
Baseline design	0.10	0.00	\$ 18,000			\$ 18,000
Analysis & optimization	0.25	0.02	\$ 48,000			\$ 48,000
Assembly drawings	0.08	0.08	\$ 26,400			\$ 26,400
Tooling (Design, M&S and Ass'y)						
Mandrel	0.02	0.05	\$ 11,100	\$ 17,594	\$ 20,585	\$ 31,685
Cavity	0.02	0.10	\$ 18,600	\$ 8,744	\$ 10,230	\$ 28,830
Reaction	0.04	0.10	\$ 22,200	\$ 18,000	\$ 21,060	\$ 43,260
Potting	0.02	0.10	\$ 18,600	\$ 3,600	\$ 4,212	\$ 22,812
Splice	0.02	0.10	\$ 18,600	\$ 1,728	\$ 2,022	\$ 20,622
Ground insulation fixture	0.02	0.05	\$ 11,100	\$ 5,040	\$ 5,897	\$ 16,997
Parts (design and procurement)						
Strand			\$ 43,200	\$ 50,544		\$ 50,544
Insulation			\$ 4,320	\$ 5,054		\$ 5,054
Coil (wedges, spacers)	0.02	0.17	\$ 29,100	\$ 46,080	\$ 53,914	\$ 83,014
Curing epoxy			\$ 2,880	\$ 3,370		\$ 3,370
Splices	0.02	0.04	\$ 9,600	\$ 5,040	\$ 5,897	\$ 15,497
Ground insulation	0.02	0.03	\$ 8,100	\$ 2,880	\$ 3,370	\$ 11,470
Quench Heaters and traces	0.02	0.04	\$ 9,600	\$ 1,440	\$ 1,685	\$ 11,285
Impregnation epoxy			\$ 7,200	\$ 8,424		\$ 8,424
Shell	0.01	0.02	\$ 4,800	\$ 11,520	\$ 13,478	\$ 18,278
Yoke	0.02	0.04	\$ 9,600	\$ 12,000	\$ 14,040	\$ 23,640
Pads/inserts	0.02	0.04	\$ 9,600	\$ 18,000	\$ 21,060	\$ 30,660
Z-rods, end plates	0.02	0.04	\$ 9,600	\$ 8,640	\$ 10,109	\$ 19,709
Bladders/keys	0.00	0.02	\$ 3,000	\$ 4,320	\$ 5,054	\$ 8,054
Instrumentation, drawings, connectors	0.10	0.10	\$ 33,000	\$ 2,880	\$ 3,370	\$ 36,370
Fabrication						
Cable fabrication	0.02	0.05	\$ 11,100		\$ -	\$ 11,100
Cable cleaning and Insulation		0.05	\$ 7,500		\$ -	\$ 7,500
Coil winding/curing	0.20	0.50	\$ 111,000		\$ -	\$ 111,000
Mechanical model assembly/test/analysis	0.10	0.20	\$ 48,000	\$ 3,000	\$ 3,510	\$ 51,510
Reaction	0.04	0.25	\$ 44,700		\$ -	\$ 44,700
Splicing, instrumentation	0.04	0.12	\$ 25,200		\$ -	\$ 25,200
Potting	0.06	0.24	\$ 46,800		\$ -	\$ 46,800
Sub-Assembly (pads)	0.01	0.02	\$ 4,800		\$ -	\$ 4,800
Shell/yoke Assembly	0.01	0.02	\$ 4,800		\$ -	\$ 4,800
Final Assembly (cold mass)	0.02	0.05	\$ 11,100		\$ -	\$ 11,100
Electricals	0.01	0.02	\$ 4,800		\$ -	\$ 4,800
Travelers/Procedures	0.08	0.16	\$ 38,400		\$ -	\$ 38,400
Production reports	0.04	0.00	\$ 7,200		\$ -	\$ 7,200
Assembly data analysis	0.08	0.00	\$ 14,400		\$ -	\$ 14,400
Test						
Test preparations	0.10	0.10	\$ 33,000		\$ -	\$ 33,000
Magnet test	0.10	0.20	\$ 48,000	\$ 20,000	\$ 23,400	\$ 71,400
Analysis and reporting	0.10	0.00	\$ 18,000		\$ -	\$ 18,000
Total			\$ 797,400	\$ 290,284	\$ 1,087,684	

1,088 k\$



Superconducting Magnet Group

Paolo Ferracin



LARP


Step 2: TQ4L-1

TQ4L-1	FTE P/E	FTE D/T	Labor	M&S	M&S+G&A	Total
Design & Analysis						
Baseline design	0.15	0.02	\$ 30,000			\$ 30,000
Analysis & optimization	0.05	0.08	\$ 21,000			\$ 21,000
Assembly drawings						
Tooling (Design, M&S and Ass'y)						
Mandrel			\$ -			\$ -
Cavity			\$ -			\$ -
Reaction			\$ -			\$ -
Potting			\$ -			\$ -
Splice			\$ -			\$ -
Ground insulation fixture			\$ -			\$ -
Parts (design and procurement)						
Strand				\$ -		\$ -
Insulation				\$ -		\$ -
Coil (wedges, spacers)			\$ -			\$ -
Curing epoxy				\$ -		\$ -
Splices	0.02	0.04	\$ 9,600	\$ 5,000	\$ 5,850	\$ 15,450
Ground insulation		0.02	\$ 3,000	\$ 3,400	\$ 3,978	\$ 6,978
Quench Heaters and traces			\$ -			\$ -
Impregnation epoxy				\$ -		\$ -
Shell			\$ -			\$ -
Yoke			\$ -			\$ -
Pads/inserts			\$ -			\$ -
Z-rods, end plates			\$ -			\$ -
Bladders/keys	0.00	0.02	\$ 3,000	\$ 4,000	\$ 4,680	\$ 7,680
Instrumentation, drawings, connectors	0.00	0.05	\$ 7,500	\$ 2,000	\$ 2,340	\$ 9,840
Fabrication						
Cable fabrication			\$ -			\$ -
Cable cleaning and Insulation			\$ -			\$ -
Coil winding/curing			\$ -			\$ -
Mechanical model assembly/test/analysis			\$ -			\$ -
Reaction			\$ -			\$ -
Splicing, instrumentation			\$ -			\$ -
Potting			\$ -			\$ -
Sub-Assembly (pads)	0.01	0.02	\$ 4,800			\$ 4,800
Shell/yoke Assembly	0.01	0.02	\$ 4,800			\$ 4,800
Final Assembly (cold mass)	0.02	0.05	\$ 11,100			\$ 11,100
Electricals	0.01	0.02	\$ 4,800			\$ 4,800
Travelers/Procedures	0.00	0.05	\$ 7,500			\$ 7,500
Production reports	0.04	0.00	\$ 7,200			\$ 7,200
Assembly data analysis	0.08	0.00	\$ 14,400			\$ 14,400
Test						
Test preparations	0.10	0.10	\$ 33,000			\$ 33,000
Magnet test	0.10	0.20	\$ 48,000	\$ 20,000	\$ 23,400	\$ 71,400
Analysis and reporting	0.10	0.00	\$ 18,000			\$ 18,000
Total			\$ 227,700	\$ 40,248	\$ 267,948	268 k\$



Superconducting Magnet Group

Paolo Ferracin



LARP

Step 2: TQ1c


TQ1c - new inner	FTE P/E	D/T	Labor	M&S	M&S+G&A	Total
Design & Analysis						
Baseline design	0.05		\$ 9,000			\$ 9,000
Analysis & optimization	0.10	0.02	\$ 21,000			\$ 21,000
Assembly drawings			\$ -			\$ -
Tooling (Design, M&S and Ass'y)						
Mandrel			\$ -			\$ -
Cavity			\$ -			\$ -
Reaction			\$ -			\$ -
Potting			\$ -			\$ -
Splice			\$ -			\$ -
Ground insulation fixture			\$ -			\$ -
Tooling modifications/optimization	0.02	0.05	\$ 11,100	\$ 5,000	\$ 5,850	\$ 16,950
Parts (design and procurement)						
Strand				\$ 30,000	\$ 35,100	\$ 35,100
Insulation				\$ 3,000	\$ 3,510	\$ 3,510
Coil (wedges, spacers)	0.02	0.15	\$ 26,100	\$ 32,000	\$ 37,440	\$ 63,540
Curing epoxy				\$ 2,000	\$ 2,340	\$ 2,340
Splices				\$ 3,500	\$ 4,095	\$ 4,095
Ground insulation	0.03		\$ 4,500	\$ 2,000	\$ 2,340	\$ 6,840
Quench Heaters and traces	0.04		\$ 6,000	\$ 1,000	\$ 1,170	\$ 7,170
Impregnation epoxy				\$ 5,000	\$ 5,850	\$ 5,850
Shell			\$ -			\$ -
Yoke			\$ -			\$ -
Pads/inserts			\$ -			\$ -
Z-rods, end plates			\$ -			\$ -
Bladders/keys			\$ -	\$ 3,000	\$ 3,510	\$ 3,510
Instrumentation, drawings, connectors			\$ -	\$ 2,000	\$ 2,340	\$ 2,340
Fabrication						
Cable fabrication	0.02	0.05	\$ 11,100			\$ 11,100
Cable cleaning and Insulation		0.05	\$ 7,500			\$ 7,500
Coil winding/curing	0.10	0.40	\$ 78,000			\$ 78,000
Mechanical model assembly/test/analysis			\$ -			\$ -
Reaction	0.04	0.20	\$ 37,200			\$ 37,200
Splicing, instrumentation	0.04	0.12	\$ 25,200			\$ 25,200
Potting	0.06	0.24	\$ 46,800			\$ 46,800
Sub-Assembly (pads)	0.01	0.02	\$ 4,800			\$ 4,800
Shell/yoke Assembly	0.01	0.02	\$ 4,800			\$ 4,800
Final Assembly (cold mass)	0.02	0.05	\$ 11,100			\$ 11,100
Electricals	0.01	0.02	\$ 4,800			\$ 4,800
Travelers/Procedures	0.05	0.10	\$ 24,000			\$ 24,000
Production reports	0.04	0.00	\$ 7,200			\$ 7,200
Assembly data analysis	0.08	0.00	\$ 14,400			\$ 14,400
Test						
Test preparations	0.05	0.05	\$ 16,500			\$ 16,500
Magnet test	0.10	0.20	\$ 48,000	\$ 20,000	\$ 23,400	\$ 71,400
Analysis and reporting	0.10	0.00	\$ 18,000			\$ 18,000
Total			\$ 437,100		\$ 126,945	\$ 564,045

564 k\$



Superconducting Magnet Group

Paolo Ferracin



LARP

Step 4: TQ4L-2


TQ4L-2	FTE		Labor		M & S	M & S+G&A	Total
	P/E	D/T	\$	-	\$	\$	
Design & Analysis							
Baseline design	0.15	0.02	\$	-			\$ -
Analysis & optimization	0.05	0.08	\$	30,000			\$ 30,000
Assembly drawings			\$	21,000			\$ 21,000
Tooling (Design, M&S and Ass'y)							
Mandrel			\$	-			\$ -
Cavity			\$	-			\$ -
Reaction			\$	-			\$ -
Potting			\$	-			\$ -
Splice			\$	-			\$ -
Ground insulation fixture			\$	-			\$ -
Parts (design and procurement)							
Strand					\$	-	\$ -
Insulation					\$	-	\$ -
Coil (wedges, spacers)			\$	-	\$	-	\$ -
Curing epoxy					\$	-	\$ -
Splices			\$	-	\$	-	\$ -
Ground insulation			\$	-	\$	-	\$ -
Quench Heaters and traces			\$	-	\$	-	\$ -
Impregnation epoxy			\$	-	\$	-	\$ -
Shell			\$	-	\$	-	\$ -
Yoke			\$	-	\$	-	\$ -
Pads/inserts			\$	-	\$	-	\$ -
Z-rods, end plates			\$	-	\$	-	\$ -
Bladders/keys	0.00	0.02	\$	3,000	\$	4,000	\$ 4,680
Instrumentation, drawings, connectors	0.00	0.05	\$	7,500	\$	2,000	\$ 2,340
Fabrication							
Cable fabrication			\$	-	\$	-	\$ -
Cable cleaning and Insulation			\$	-	\$	-	\$ -
Coil winding/curing			\$	-	\$	-	\$ -
Mechanical model assembly/test/analysis			\$	-	\$	-	\$ -
Reaction			\$	-	\$	-	\$ -
Splicing, instrumentation			\$	-	\$	-	\$ -
Potting			\$	-	\$	-	\$ -
Sub-Assembly (pads)	0.01	0.02	\$	4,800			\$ 4,800
Shell/yoke Assembly	0.01	0.02	\$	4,800			\$ 4,800
Final Assembly (cold mass)	0.02	0.05	\$	11,100			\$ 11,100
Electricals	0.01	0.02	\$	4,800			\$ 4,800
Travelers/Procedures	0.00	0.05	\$	7,500			\$ 7,500
Production reports	0.04	0.00	\$	7,200			\$ 7,200
Assembly data analysis	0.08	0.00	\$	14,400			\$ 14,400
Test							
Test preparations	0.10	0.10	\$	33,000			\$ 33,000
Magnet test	0.10	0.20	\$	48,000	\$ 20,000	\$ 23,400	\$ 71,400
Analysis and reporting	0.10	0.00	\$	18,000			\$ 18,000
Total			\$	215,100		\$ 40,248	\$ 255,348

255 k\$



Superconducting Magnet Group

Paolo Ferracin



LARP


Schedule

	FY06				FY07			
	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
TQ1b	Design							
		Fab. outer double layer tooling and structure		Fab. TQ1b coil	Ass./ test TQ1b			
TQ4L-2						Ass./ test TQ1a + TQ1b		
TQ1c					Fab. TQ1c coil		Ass./ test TQ1c	
TQ4L-2								Ass./ test TQ1c + TQ1b



Superconducting Magnet Group

Paolo Ferracin



LARP

Conclusions

- A four-layer design addresses the stated **LARP** goals
- Gradient above **300 T/m** (90 mm bore)
- Peak field close to **16 T**
- Magnet developed with intermediate **steps**
 - More flexibility and lower risk
 - Outer layer with **130 mm aperture** and **14.5 T** peak field



Superconducting Magnet Group

Paolo Ferracin