



US LHC Accelerator Research Program

bnl - fnal- lbnl - slac

TQ Objectives and Features

LARP Collaboration Meeting 4

Port Jefferson, April 6-8, 2005

Gian Luca Sabbi



Magnet R&D FY05-FY09

	Length	Aperture	FY05	FY06	FY07	FY08	FY09
	[m]	[mm]					
Model Magnets							
Quads							
Reduced Gradient (costheta)		90		XX			
Full gradient (costheta)	1	90		X	X	X	
Large Aperture Quad	1	~120			X	XX	X
Field quality	2						XX
Full length, full gradient	4						X
Dipoles							
Open mid-plane PoP	1					X	X
Supporting R&D							
Sub-scale tests			XX	XX	XX	XXX	XX
Long coil tests					X	X	

Today's
focus

Thursday's
focus



Three-year Plan (LAPAC, 6/04)

The following objectives have been established for FY05-FY07:

1. **Design, fabricate and test simplified “Technology Quads”**
 - ↳ **Explore different options for coil and structure**
 - ↳ **Select the baseline quadrupole design**
2. Design, fabricate and test simplified “technology dipoles”
 - ⇒ Explore the feasibility of the open mid-plane approach
3. Demonstrate Nb₃Sn wind-and-react length scale-up



Technology Plan (LAPAC)

- **Fabrication and test of a simplified cos2q quad:**

- ⇒ inner or outer double-layer of a four-layer design
- ⇒ 90 mm (inner) bore for risk & cost reduction
- ⇒ joint effort LBNL+FNAL (design/fab) & BNL (test)

- **Fabrication and test of one subscale model:**

- ⇒ two proposals, dipole or quadrupole: discuss and select
- ⇒ joint effort LBNL (design/fab) + BNL (design/fab/test)
- ⇒ work not funded in FY05 will be considered for FY06
- ⇒ options to increase the scope at low cost (strand tests etc.)

- **Conductor development**

- ⇒ support TQ(4L)1a and prepare for FY06



Basic R&D Tasks (LAPAC)

- **Mechanical structures for quadrupoles and dipoles:**
 - ⇒ Support Lorentz forces, deliver required pre-stress
 - ⇒ Limit the stress on the conductor
 - ⇒ Limit the radiation heat deposition
 - ⇒ Satisfy field quality and alignment requirements
- Superconducting wires and cables (coord. w/DOE Program)
 - ⇒ Electrical and mechanical stability
 - ⇒ Degradation due to cabling and stress
- Length scale-up for Nb₃Sn wind-and-react technology
 - ⇒ Fabrication, handling and support of long coils



Shell-based Structure

Concept:

- Aluminum shell over yoke and pads
- Assembly based on bladders and keys

Advantages:

- Can deliver very high pre-stress
- Large pre-stress increase at cool-down
- Easy assembly/disassembly/reassembly

R&D issues:

- Coil alignment, field quality
- Long vs. segmented shells



Mechanical test (FY04)



Collar-based Structure

Concept:


- Support by thick SS collars
- Assembly w/external press

Advantages:

- Proven coil positioning
- Proven length scale-up

R&D issues:

- Deliver required pre-stress
- Pre-stress overshoot
- Flexibility for R&D





TQ Plan for FY05(06)

Develop two short models using the same coil design and different mechanical support concepts:

- TQ1a: shell-based structure
- TQ2a: collar-based structure

Coil design:

- Simple double-layer w/conservative cable parameters
- 90 mm aperture, 1 m total length

Objectives: feedback on cable, coil and structure development

- check basic design/fabrication, demonstrate quench performance
- study mechanical structure, conductor, quench protection issues
- evaluate (keystoned) cable performance: stability, stress




TQ1a/2a Conductor & Coil Design

Conductor:

- 0.7 mm strand (**RRP/MJR**)
- 27 (**± 1**) strands
- 1.0 degrees keystone
- Width: 10.05 mm
- Mid-thickness: 1.26 mm
- Insulation: S-2 glass sleeve

Coil:

- double-layer shell
- one (inner layer) wedge/octant



TQ1a/2a coil cross-section



TQ1a Milestones (Task Sheet)

Work Plan, Distribution, and Schedule:

FY05

- | | | |
|--|------------|------------|
| - Design of cable, coil, and tooling: | FNAL+LBNL; | 02/28/2005 |
| - Fabricate/Insulate cable: | LBNL; | 04/01/2005 |
| - Procure coil fabrication tooling/parts: | FNAL; | 04/15/2005 |
| - Design and fabricate pad inserts | LBNL | 04/31/2005 |
| - Design and fabricate axial rods + end plates | LBNL | 04/31/2005 |
| - Fabricate practice coil: | FNAL+LBNL; | 06/25/2005 |
| - Wind/cure coils: | FNAL+LBNL; | 08/25/2005 |
| - React/impregnate coils: | LBNL; | 10/15/2005 |

FY06

- | | | |
|--------------------|-------|------------|
| - Assemble magnet: | LBNL; | 12/15/2005 |
| - Test magnet: | BNL; | 02/01/2006 |



TQ2a Milestones (Task Sheet)

Work Plan, Distribution, and Schedule:

FY05

- | | | |
|---|------------|------------|
| - Design of cable, coil, and tooling: | FNAL+LBNL; | 02/28/2005 |
| - Fabricate insulated cable: | LBNL; | 04/01/2005 |
| - Procure coil fabrication tooling/parts: | FNAL; | 04/15/2005 |
| - Fabricate practice coil: | FNAL+LBNL; | 06/25/2005 |
| - Procure collars (modified from MQXB): | FNAL; | 06/15/2005 |
| - Assemble and test mechanical model: | FNAL; | 08/15/2005 |
| - Wind and cure coils: | FNAL; | 10/25/2005 |

FY06

- | | | |
|-------------------------------|-------|------------|
| - React and impregnate coils: | FNAL; | 12/25/2005 |
| - Assemble magnet: | FNAL; | 02/15/2006 |
| - Test magnet: | BNL; | 03/31/2006 |



TQ1a & TQ2a Budget

TQ1a	LARP		Base Program		Total
	FY05	FY06	FY05	FY06	
FNAL	236	0	0	0	236
LBNL	329	42	0	0	371
BNL	24	89	0	0	113
Total	589	131	0	0	720

TQ2a	LARP		Base Program		Total
	FY05	FY06	FY05	FY06	
FNAL	150	344	234	0	728
LBNL	36	0	0	0	36
BNL	23	89	0	0	112
Total	209	433	234	0	876



BNL

FY05 FY06

TQ2a
specific



TQ1a cost baseline

TQ1a cost baseline	FTE		Labor	M&S	M&S+G&A	Total
	P/E	D/T				
Design & Analysis						
Baseline design	0.10	0.00	\$ 18,000			\$ 18,000
Analysis & optimization	0.25	0.02	\$ 48,000			\$ 48,000
Assembly drawings	0.08	0.08	\$ 26,400			\$ 26,400
Tooling (Design, M&S and Ass'y)						\$ -
Mandrel	0.02	0.08	\$ 15,600	\$ 12,218	\$ 14,295	\$ 29,895
Cavity	0.04	0.12	\$ 25,200	\$ 6,072	\$ 7,104	\$ 32,304
Reaction	0.04	0.10	\$ 22,200	\$ 12,500	\$ 14,625	\$ 36,825
Potting	0.02	0.10	\$ 18,600	\$ 2,500	\$ 2,925	\$ 21,525
Splice	0.02	0.10	\$ 18,600	\$ 1,200	\$ 1,404	\$ 20,004
Ground insulation fixture	0.02	0.10	\$ 18,600	\$ 3,500	\$ 4,095	\$ 22,695
Parts (design and procurement)						
Strand				\$ 40,000	\$ 46,800	\$ 46,800
Insulation				\$ 5,000	\$ 5,850	\$ 5,850
Coil (wedges, spacers)	0.02	0.17	\$ 29,100	\$ 64,500	\$ 75,465	\$ 104,565
Curing epoxy				\$ 3,500	\$ 4,095	\$ 4,095
Splices	0.02	0.04	\$ 9,600	\$ 7,000	\$ 8,190	\$ 17,790
Ground insulation	0.02	0.03	\$ 8,100	\$ 3,400	\$ 3,978	\$ 12,078
Quench Heaters and traces	0.02	0.04	\$ 9,600	\$ 1,000	\$ 1,170	\$ 10,770
Impregnation epoxy				\$ 5,000	\$ 5,850	\$ 5,850
Shell	0.02	0.04	\$ 9,600	\$ 8,000	\$ 9,360	\$ 18,960
Yoke	0.02	0.04	\$ 9,600	\$ 8,000	\$ 9,360	\$ 18,960
Pads/inserts	0.02	0.04	\$ 9,600	\$ 8,000	\$ 9,360	\$ 18,960
Z-rods, end plates	0.02	0.04	\$ 9,600	\$ 6,000	\$ 7,020	\$ 16,620
Bladders/keys	0.00	0.02	\$ 3,000	\$ 3,000	\$ 3,510	\$ 6,510
Instrumentation, drawings, connectors	0.10	0.10	\$ 33,000	\$ 2,000	\$ 2,340	\$ 35,340
Fabrication						
Cable fabrication	0.02	0.05	\$ 11,100		\$ -	\$ 11,100
Cable cleaning and Insulation		0.05	\$ 7,500		\$ -	\$ 7,500
Coil winding/curing	0.20	0.50	\$ 111,000		\$ -	\$ 111,000
Mechanical model assembly/test/analysis	0.10	0.20	\$ 48,000	\$ 3,000	\$ 3,510	\$ 51,510
Reaction	0.04	0.25	\$ 44,700		\$ -	\$ 44,700
Splicing, instrumentation	0.04	0.12	\$ 25,200		\$ -	\$ 25,200
Potting	0.06	0.24	\$ 46,800		\$ -	\$ 46,800
Sub-Assembly (pads)	0.01	0.02	\$ 4,800		\$ -	\$ 4,800
Shell/yoke Assembly	0.01	0.02	\$ 4,800		\$ -	\$ 4,800
Final Assembly (cold mass)	0.02	0.05	\$ 11,100		\$ -	\$ 11,100
Electricals	0.01	0.02	\$ 4,800		\$ -	\$ 4,800
Travelers/Procedures	0.08	0.16	\$ 38,400		\$ -	\$ 38,400
Production reports	0.04	0.00	\$ 7,200		\$ -	\$ 7,200
Assembly data analysis	0.08	0.00	\$ 14,400		\$ -	\$ 14,400
Test						
Test preparations	0.10	0.10	\$ 33,000		\$ -	\$ 33,000
Magnet test	0.10	0.20	\$ 48,000	\$ 20,000	\$ 23,400	\$ 71,400
Analysis and reporting	0.10	0.00	\$ 18,000		\$ -	\$ 18,000
Total			\$ 820,800		\$ 263,706	\$ 1,084,506

1,084 k\$



LAPAC Closeout Comments (1)

Organization/management:

*...Fermilab and LBNL have now developed parallel experiences on the manufacturing of Nb_3Sn coils and it might be worthwhile to **compare and reconcile these experiences**, so as to develop common procedures at the two laboratories for both the subscale and the model magnet programs.*

*...we have seen a good horizontal integration of effort by phases; e.g. one lab designs, one assembles, and third tests. **Integration of effort on individual phases**, while stated to be planned, was not evident at this time. The program will benefit greatly if this was improved.*



LAPAC Closeout Comments (2)

Technical program:

*...the committee concurs that it is beneficial to build identical short model magnets, rather than to investigate **variants which may be too difficult to compare** and draw any relevant conclusion.*

...the 90 mm aperture seems a “conservative” and reasonable choice to begin with.

*...there has been progress in **focusing efforts on fewer options** before proceeding with hardware tests, but in the option of the LAPAC more effort is needed in this area.*



TQ1a/2a Development Issues (1)

Adequate communication flow is required to work efficiently across labs:

- *Much improvement in the last months, but we are not quite there yet*
- *Tele/video conferences have been very useful, but limited*
- *Technical progress discussions/review in 2 weeks*

Better definition of responsibilities is also needed to improve rate of progress:

- *Example/model: cable development & fabrication*
- *Materials experts provide data and advice*
- *Task leaders are responsible to take decisions and meet schedule*
- *Should be addressed at collaboration meeting*

Implications of the use of different conductors for TQ1a and TQ2a:

- *Behaviour may differ with respect to stability*
- *Target gradients/field/stress may be different*
- *Address at progress review meeting*



TQ1a/2a Development Issues

Implications of different pre-load strategies for TQ1a and TQ2a:

- *Goal: compare mechanical structures, not coil support philosophies*
- *Address at progress review meeting*

Specifics of coil fabrication procedures and tooling need further discussion

- *Will be discussed at progress review meeting*
- *Further opportunities during practice coil fabrication*

Transfer of tooling across labs for coil reaction/impregnation:

- *Implications on schedule have not been looked at in detail*

Test planning & preparations

- *Will be addressed by integration group*



Summary

- The TQ program has developed in a way consistent with LAPAC
- All three labs provide essential contributions
- Converged on the same coil design for both models
- No significant cost overruns so far
- Good progress on design and procurements
- Several issues need to be addressed in order to:
 - maintain/improve rate of progress
 - make sure we address the final objectives

Rate of progress and successful completion of TQ1a and TQ2a are essential benchmarks towards meeting the FY09 targets