




*BNL - FNAL - LBNL - SLAC*

## **LARP BEAM INSTRUMENTATION**

A. Ratti  
LBNL

Presented at the LARPAC meeting

Brookhaven  
May 10-12, 2006



**LARP**

## Outline

Overview of existing instruments

Schottky Monitor (lead by FNAL)


Tune Feedback (lead by BNL)

Luminosity Monitor (lead by LBNL)

Common instrumentation issues

Data Acquisition

Documentation and integration at CERN



**LARP**

## Highlights

From Steve's highlights:


Simultaneous tune and coupling feedback was demonstrated in RHIC - a world first

US colliders are an essential part of the LARP contribution to the LHC

Developing all instruments with experimental support of colliding beam operations

Documentation, integration issues are becoming more urgent and being addressed with a systematic approach both within the LARP and the CERN (EDMS) frameworks

Year by year funding needs to be managed closely



**LARP**

## Introduction

### Three instruments at different levels of maturity

Schottky monitors will be mostly completed by the end of FY06


Luminosity monitors will be under production through 06 and into 07

Tune and coupling feedback are still under development and will reach a final design in early FY07

All three devices are on schedule to support LHC commissioning

The data acquisition platform is defined by CERN and therefore common to all LARP instruments - Held a successful workshop on April 25, 2006






**LARP**

## Schottky Monitors

Advanced enabling technology for:

- Non invasive tune measurement for each ring
- Non invasive chromaticity measurements
- Measure momentum spread
- Continuous online emittance monitor
- Measure beam-beam tune shift

Build in capability to monitor gain variation with time  
Measure individual or multiple bunches



**LARP**

## Technical Approach

Center frequency of 4.8 GHz

3dB BW - 300 MHz

Sufficient for 25ns bunch spacing

Small longitudinal Z/n

No absorbers allowed

Below frequency of Schottky band overlap

Allows for adequate physical aperture

Matched pairs of SiO<sub>2</sub> Coax cables







Table 1. Parameters of LHC Schottky Pickup (unit: mm)


Slot length	Slot width	Slot Spacing	Number of Slots	Waveguide width	Waveguide height	Beam pipe width	Beam pipe height
20.52	2.032	2.032	246	47.549	22.149	60.00	60.00



**LARP**


## Pickup and Adjacent Beampipe






**LARP**


## Mode Launcher Impedance






**LARP**

## Mode Launcher Response





**LARP**


## Connections and Processing


Feedthroughs and tunnel connections  
are critical

CERN ordering the coaxial cables

FNAL provided detailed layouts for  
phase matched cables

Installation planned in point 4 of LHC







**LARP**


## Tevatron Experience

*Tevatron Single Bunch Horizontal Protons*



*60 Hz Modulation on Tevatron Schottky Signals*






**LARP**


## Schottky Measurements at Tevatron

Allows measurements of:

- Tunes from peak positions
- Momentum spread from average width
- Chromaticity from differential width
- Emittance from average band power









**LARP**

# Schottky Electronics Block Diagram





**LARP**

## Schottky Processing Electronics


Dual downconversion preserves single sideband signal with Chromaticity information

First IF at 45 MHz, using a LO locked to the 40MHz LHC clock reference

Crystal filter selects a 15 kHz band of schottky signal

Second IF takes the signal down to DC-80KHz baseband

Data is then collected with 20-24 bits CERN DAQ cards in DAB-IV environment



**LARP**

## Schottky Monitor - Roles and Responsibilities

### FNAL/BNL


- Deliver a complete, ready to print drawing package to CERN
- Deliver a full set of front end electronics to connect to the detectors
- Provide installation and hardware commissioning support

### CERN

- Build beamline devices to FNAL's prints
- Provide local cabling, installation,
- Local Oscillators, Reference signals, Data Acquisition hardware
- Final integration with control system

### LARP - Commissioning

- The beam commissioning of these devices will be supported by the Beam Commissioning group



**LARP**

## Schottky Planning

FY06

Final Design Review at CERN on June 22

Lots of other integration activities as well

CERN fabricates and installs the devices in the LHC

Summer 2006, depending upon LHC's installation schedule

All cables have been specified and requested


Including request for timing and synchronization signals

FNAL will build the analog processing electronics during the summer

FY07

Activities include hardware commissioning and installation support

In particular two trips to CERN, one to test the hardware without beam, and the next to test with beam (when beam occurs)



**LARP**

# LUMI - Requirements

## Requirements (Lumi mini Workshop, 16-17 Apr. 99)

- Absolute  $L$  measurement with  $\delta L/L \sim 5\%$  for  $L > 10^{30} \text{ cm}^{-2}\text{sec}^{-1}$
- Cross calibration with LHC experiment measurements of  $L$  (every few months)
- Sensitivity of  $L$  measurement to variations of IP position ( $x^*, y^* < 1\text{mm}$ ) and crossing angle ( $x^*, y^* < 10\mu\text{rad}$ ) less than 1%
- Dynamic range with "reasonable" acquisition times for 1% precision to cover  $10^{28} \text{ cm}^{-2} \text{ sec}^{-1}$  to  $10^{34} \text{ cm}^{-2} \text{ sec}^{-1}$
- Capable of use to keep machine tuned within  $\sim 2\%$  of optimum  $L$
- Bandwidth 40 MHz to resolve the luminosity of individual bunches
- Backgrounds less than 10% of the  $L$  signal and correctable

LBNL  
25 Jan. 2002

40 MHz Ionization Chamber  
W.C. Turner

11

Help bring beams into collisions too



# LUMI - Specification

CERN  
CH-1211 Geneva 23  
Switzerland



the  
Large  
Hadron  
Collider  
project

LHC Project Document No.  
**LHC-B-ES-0007 rev 0.4**

CERN Discharge of Supplier/Contractor Document No.

**AB-BDI**

EDMS Document No.  
**347396**

Date: 2003-06-11

## Functional Specification

### MEASUREMENT OF THE RELATIVE LUMINOSITY AT THE LHC

#### Abstract

This functional specification defines the requirements for the measurement and optimization of the interaction rates or relative luminosity at the four LHC interaction points. The beam and machine scenarios and the anticipated uses in operation are analysed to define the required dynamic ranges, precision, time response,... of the machine luminometers. The potential for absolute calibration, the complementarities with the experimental absolute luminometers and the data exchange between machine and experiments are discussed and specified. The requirement for the measurement of the background to the experiments by standardized detectors was identified and will be dealt with in a separate document.

Prepared by	Checked by :	Approval Leader :
<b>R. Assmann/AB-ABP</b> <b>J.P. Koutchouk/AB-BDI</b> <b>M. Placidi/AB-BDI</b> <b>E. Tsesselis/EST-LEA</b>	<b>Oliver Brüning [AB/ABP]</b> <b>J-Jacques Gras [AB/BDI]</b> <b>Rüdiger Schmidt [AB/CO]</b> <b>Jörg Wenninger [AB/OP]</b>	
<b>Approval Group Members</b> LTC: S. Myers, P. Collier; AB/ABP: J.-P. Riinaud, S. Fartoukh, W. Herr, F. Ruggiero; AB/BDI: H. Schmickler, R. Jung, E. Bravin, W.C. Turner; AB/OP: S. Baird, K. Cornelis; EST/LEA: K. Potter; ALICE: D. Evans, C. Fabjan, L. Leistam, A. Morsch; ATLAS: N. Ellis, P. Grafstrom, M. Nessi; CMS: A. Ball, A. Herve, M. Huhtinen, W. Smith; LHCb: R. Jacobsson, A. Smith, W. Witzeling; TOTEM: M. Bozzo, K. Eggert, D. Macina, M. Oriunno;		

#### Prepared by

**R. Assmann/AB-ABP**  
**J.P. Koutchouk/AB-BDI**  
**M. Placidi/AB-BDI**  
**E. Tsesselis/EST-LEA**

#### Checked by :

**Oliver Brüning [AB/ABP]**  
**J-Jacques Gras [AB/BDI]**  
**Rüdiger Schmidt [AB/CO]**  
**Jörg Wenninger [AB/OP]**


#### Approval Leader :

#### Approval Group Members

**LTC:** S. Myers, P. Collier; **AB/ABP:** J.-P. Riinaud, S. Fartoukh, W. Herr, F. Ruggiero;  
**AB/BDI:** H. Schmickler, R. Jung, E. Bravin, W.C. Turner; **AB/OP:** S. Baird, K. Cornelis;  
**EST/LEA:** K. Potter;  
**ALICE:** D. Evans, C. Fabjan, L. Leistam, A. Morsch; **ATLAS:** N. Ellis, P. Grafstrom, M. Nessi;  
**CMS:** A. Ball, A. Herve, M. Huhtinen, W. Smith; **LHCb:** R. Jacobsson, A. Smith, W. Witzeling;  
**TOTEM:** M. Bozzo, K. Eggert, D. Macina, M. Oriunno;




## LUMI - Conceptual Design Argon Ionization Chamber



Signal is proportional to the number of parallel gaps  
Capacitance add up with n. of gaps + slows down the signal

- Optimized for 6 gaps
- Must live in a radiation environment 100x worse than accelerator instruments have ever seen
  - $\sim 10\text{Gy/yr}$ ,  $\sim 10^{18}\text{ N/cm}^2$  over lifetime (20 yrs),  $\sim 10^{16}\text{ p/cm}^2$  over lifetime



**LARP**

## LUMI Status

Final design complete

Successful design review on April 24, 2006

Most critical R&D parameters demonstrated

Successful high speed (40 MHz test) using X-ray  
beamline at ALS


Final design presented here

Some R&D still ongoing

Testing prototype in RHIC

Rad damage tests underway






*LARP*


## FDR results

### Excellent review

- Highlighted several areas of possible improvement
- Endorsed basic design
- Recognized progress
- Recommended fast path to production



Final report not available yet



**LARP**

## Testing at RHIC

RHIC run was suddenly restored

Presented plan at RHIC APAX meeting in November

Asked for 2 shifts of 3-4 hours each

Need dedicated collisions

Now setup in IR10, former PHOBOS area


While ideal running condition is Au-Au, this run is p-p

We'll focus on backgrounds and on establishing operation of the device - 250 GeV will help

Infinuim scope we can watch from LBL

Plan to use in parasitic mode while RHIC is running

Plan to replace with lumi DAQ system



**LARP**

## Mechanical Design

Ready for final prints and production


Performed thermal and stress analysis

Performed gas flow modeling through the chamber

Completely revised the housing and fabrication




Detector nearly identical to the prototype

Fabrication process defined




**LARP**


Case is designed to manage stress levels



**K. Chow**




Max stress is <16kpsi (<110 MPa)




# Gas flow through ionization chamber

**LARP**

Detail of ionization chamber without copper bar




With support plate displaced in beam direction




4 gas inlet holes on support plate

Chamber gas flow volume model



**K. Chow**


120 holes in ground plane, 1 mm diameter each




**LARP**

## Gas velocity in production chamber

Velocity  
(Contour 1)




[m s<sup>-1</sup>]




This face is at a cut  
plane through center of  
front gas volume

**K. Chow**

Darkest blue areas are  
equivalent to less than 0.017  
liter per hour flow







For comparison: gas velocities in prototype chamber

**LARP**

Prototype ionization chamber  
showing outline of 1/8 symmetric  
gas flow model




Velocity  
(Contour 1)



[m s<sup>-1</sup>]


inlet

outlets



**K. Chow**

Darkest blue areas are equivalent to less  
than 0.017 liter per hour flow



## Thermal conditions during TAN bakeout

### LARP

#### Bakeout operation

Heat up the beam tube to 200 deg C in 24 hours.

Stay at 200 deg C for a minimum of 24 hours


Ambient cooldown

Bakeout performed in situ whenever beam tube exposed to atmospheric pressure

Maximum temperature in absorber box is up to 300 deg C

#### FEA results

Temperatures after 20 hours



Details of the handling plan for LUMI are being formulated


**K. Chow**

Analysis will be used to estimate temperature rise in LUMI

Temperatures in LUMI should be monitored during bakeout (with thermocouples) to determine if it exceeds its allowable temperature

LUMI should be (partially) pulled out of slot if it may overheat (pullout has radiation exposure implications)







**LARP**

# Signal Processing


- Very low noise pre-amp in the tunnel
- Shaper section completes the analog signal processing
- ADCs integrated in a VME64 mezzanine card
  - Interface defined by CERN BDI group






**LARP**

## Electrical Connections





**LARP**

## IBMS Mezzanine Board (1)



Data from IBMS technical specifications document in EDMS (Jean-Jacques SAVIOZ)


IBMS Mezzanine Board contains:  
Custom ASIC originally developed for the LHCb Preshower detector  
14-bit digitizer (only 12 used).

### ASIC:

Dual integrator + T/H circuit  
One integrator operates while other is in reset mode.


Differential input.






**LARP**

## Shaper Board and DAB64x boards





**LARP**

## Radiation Damage to passive components

Damage to passive components is mostly dominated by neutron scattering

DPAs are a best way to measure the effects of radiation exposure


While a DPA to first order is a DPA, neutron energy, flux, temperature changes can have a great impact on test results

If an atom is displaced and quickly recombines, it could be no problem

If this happens while an enormous amount of heat is dissipated, the material properties could easily change, the atom may not recombine...

Using the DPA approach, we can use neutrons at several test facilities

Still important to have relatively high energies



**LARP**

## Rad Damage Testing at CERN

At the ISOLDE ion source with a 1.4 GeV p beam from CERN PS Booster

~ $10^{13}$  protons per second

Facility has robotic capabilities

Have prepared two identical kits


First kit will be exposed ~3 months

Second kit will be exposed ~ 9 months

After irradiation we will perform mechanical testing and metallurgical investigations of the samples.

Electrical components are in a bridge configuration for easy electrical measurements





Setting up a MARS model to calculate DPAs in this configuration and compare with LHC projections




**LARP**

## Setup at ISOLDE's source

Our samples are mounted on the wall behind the source







**LARP**

## Active Components in LUMI

In general a level of  $\sim 100$  krad/yr is tolerated by bipolar transistors

Packaging front end electronics for fast replacement

Dual channel to overcome random failures

Recommend replacement after a given integrated dose

1-2 years at highest luminosity

Earlier operation at lower luminosity will allow for a longer time before replacement

Do we have a choice??





# Integration planning at CERN

- Complete system description
  - Technical, installation, safety, electronics, responsibilities, deliverables...
- Met with all relevant parties at CERN
- Final draft at CERN
- EDMS process underway

CERN CH-1211 Geneva 23 Switzerland		LHC Project Document No. <b>LHC-</b>	
the Large Hadron Collider project		LHC Project Document No.	
Date: 1999-09-22		EDMS Document No.	
<b>Technical Specification</b>			
<b>LHC LUMINOSITY MONITOR</b>			
<b>Abstract</b>			
<p>The LHC luminosity monitors are gas ionization chambers that sample energy deposition in the forward TAN neutral particle absorbers. These luminosity monitors are primarily sensitive to high energy neutrons produced near zero degrees by pp collisions at the IP. The neutron strikes in the TAN absorbers produce hadronic-electromagnetic showers that deposit energy by ionization. The luminosity monitors are placed near the maximum of shower energy deposition in the TAN absorbers. Since the flux of neutrons and shower energy deposition are proportional to luminosity, the signal strength measured by the ionization chambers provides a measurement of relative luminosity. The ionization chambers and associated electronics have been designed to measure luminosity with 40% relative accuracy, or better, in each of the four quadrants. The ionization chambers are segmented into quadrants to allow measurement of beam-beam crossing angle. Small modulation of the transverse position of one beam at the IP allows measurement of beam-beam separation at the IP. The measurement of beam-beam separation can then be used in a slow feedback loop to reduce the beam separation to zero and maintain the LHC in optimum luminosity.</p>			
<b>Prepared by:</b> [E.Bravin] [AB/BDG] [ernica.bravin@cern.ch] [A.Ratti] [LHC] [aratti@lbl.gov]		<b>Checked by:</b>	


LHC Project Document No.

**LHC-**

Page 3 of 13

## Table of Contents

<b>1. DISCLAIMER - INTRODUCTION</b>	<b>5</b>
<b>2. SYSTEM DESCRIPTION</b>	<b>5</b>
2.1 INTRODUCTION	5
2.2 GAS SYSTEM	6
2.3 HIGH VOLTAGE AND DC SYSTEMS	6
2.4 REMOTE MONITORING AND EQUIPMENT PROTECTION	6
2.5 INSTALLATION	6
<b>3. MODES OF OPERATION</b>	<b>7</b>
<b>4. OPERATING PARAMETERS</b>	<b>8</b>
<b>5. EXTERNAL CONNECTIONS</b>	<b>8</b>
5.1 GAS LINES	8
5.2 SIGNAL, CONTROLS AND HV CABLES	8
5.3 NETWORK INTERFACES	8
<b>6. SYSTEM SAFETY</b>	<b>8</b>
6.1 RADIATION SAFETY	8
6.2 COMPRESSED GASES	9
6.3 HIGH VOLTAGE	9
<b>7. GAS HANDLING SYSTEM</b>	<b>9</b>
7.1 GAS DISTRIBUTION	9
7.2 TEMPERATURE AND PRESSURE MONITORING AND RELIEF	10
7.3 COMPRESSED GAS SAFETY CONSIDERATIONS	10
7.4 GAS ANALYSIS - SPECTROSCOPY + RADIATION	10
<b>8. HIGH VOLTAGE DISTRIBUTION</b>	<b>10</b>
8.1 DC BIAS TO THE ELECTRODES	10
8.2 CONTINUITY CHECK	10
<b>9. DATA ACQUISITION SYSTEM</b>	<b>10</b>
9.1 SYSTEM INFRASTRUCTURE - THE VME DABIV BOARD	10
9.2 MEZZANINE CARD	10
9.3 FPGA PROGRAMMING	11
<b>10. CONTROL SYSTEM INTERFACE</b>	<b>11</b>
<b>11. HARDWARE COMMISSIONING</b>	<b>11</b>
11.1 HV TESTING	11
11.2 SIGNAL TESTING PROCEDURE	11
11.3 HARDWARE CHECKOUT	12
<b>12. PLANNING</b>	<b>12</b>
12.1 MILESTONES	12
12.2 RESPONSIBILITIES	12
12.3 BEAM COMMISSIONING AND BEAM REQUIREMENTS	12
<b>13. LUMINOSITY MEASUREMENTS IN IP2 AND IP8</b>	<b>12</b>



**LARP**

## Integration effort at CERN

~8 FTE-months spent at CERN in integration activities

Two integration meetings in January and March

Including an integration workshop with all groups instrumenting TAN


Opening a team account to support local expenses

Planning more visits to further plans and follow through

TS/LEA group now responsible to coordinate installation and documentation of TAN instrumentation area

Generates 3D layout of the area

Coordinates gas installation activities



**LARP**

## LUMI Long Term Plans (from 2005)

### FY06

Fabrication of first article

Design of auxiliary hardware

Device tests, electronics integration and performance qualification

Deliver first unit to CERN - **delayed ~3 months**

### FY07

Fabricate balance of units and auxiliary hardware


Transfer to CERN

Installation support

Commissioning support

### FY08

Post-commissioning and pre-operations support



**LARP**

# Tune Feedback

Challenge: persistent current effects in SC magnets can strongly perturb machine lattice, especially during energy ramp (aka “snapback”). Effects for LHC predicted to be large.


Betatron tunes ( $Q_{x,y}$ ) and chromaticities ( $Q'_{x,y} = EdQ_{x,y}/dE$ ) can vary significantly due to “snapback” resulting in beam loss, emittance growth.

**Solution: make fast, precision  $Q$ ,  $Q'$  measurements and use these signals to feedback to tuning quadrupoles and sextupoles.**

This effort is ideally suited for a collaboration with RHIC, which can be the benchmark and testing ground for this effort.


The Two Issues at RHIC:

- Dynamic Range
- Coupling



LARP




## Effects of persistent currents in RHIC (early results)




Energy increasing



# chrom - good results under sequencer control





**LARP**

## Tune Feedback - Technical Approach


### Previous RHIC approach

- resonant pickup, above the coherent spectrum
- defeated by transition - short bunches, fast orbit changes
- defeated by coupling - strong sextupoles, vertical orbit changes affect coupling, coupling drives tune feedback unstable

### New LHC (and current generation RHIC)


- direct diode detection - mix all betatron lines to baseband, solves dynamic range problem
- measure all four eigenmode projections - results in PLL that is robust in the presence of coupling

**CERN and BNL personnel are actively collaborating on tune feedback and using RHIC as a platform for developing the system**



**LARP**


## Effects of Coupling



Schematics showing the two eigenmodes rotated with respect to the horizontal and vertical planes due to coupling. The left hand figure shows the special case where the projections of each mode in each plane are in phase. The right hand side shows the more general case where coupling introduces a phase shift into the eigenmode projections.

C-A/AP/174 - Possible phase loop for the global betatron decoupling, Y. Luo et al  
 C-A/AP/204 - Towards a Robust Phase Locked Loop Tune Feedback System, R. Jones et al  
 both at [http://www.rhichome.bnl.gov/AP/ap\\_notes/cad\\_ap\\_index.html](http://www.rhichome.bnl.gov/AP/ap_notes/cad_ap_index.html)





**LARP**

# Tune and Coupling Measurements


## Tune


PLL tune measurement operational at RHIC for several years, automated, controlled by sequencer. Specialist checks status every few days.

Used for ramp tune and chrom measurements, IR corrections, machine studies,...


## Coupling


PLL re-configured to measure all four eigenmode projections results in PLL that can be made robust in the presence of coupling






## RHIC Systems Diagram






**LARP**

## Recent Success at RHIC





**LARP**

## Tune Feedback - Ongoing Activities

3D-BBQ system still suffers from phase noise problems

- very sensitive detector

- sudden phase losses

- 60 Hz lines still troublesome

### Mains Harmonics

- Excitation of betatron line by power supply ripple

- Seen at CERN, FNAL, BNL,...

- Understood for over a year

- Not a RHIC priority in higher scheme of things

- Main obstacle to further feedbacks development**

Will continue studying system performance throughout the RHIC run and finalize system design by the end of the summer

TRACE A: Ch1 Spectrum

A Marker

336.2 ks


17 274.599 2 Hz

-47.126 dBm

-20  
dBm

Mains Harmonics  
during RHIC ramping  
with no kicker  
excitation

720Hz



betatron 'line'


-120  
dBm


Center: 20.704775 kHz

Span: 9.765625 kHz

# Blue horizontal mains harmonics on ramp 5 May 2006

(from previous slide)





**LARP**

## Mains Harmonics - 12 phase balancing

BBQ noise floor  $\sim 10\text{nm}$

Mains harmonics  $\sim 70\text{dB}$  above this

$\sim 30\mu$  excitation due to mains harmonics

LHC spec is  $< 1\mu$  excitation permitted

Tune tracking requires excessive kicker power


emittance blowup

cannot do development work

need 12 phase balancing

April 05 Tune Feedback Design Review


**“12 phase balancing is highest priority”**



**LARP**

# CERN's TF requirements

**CERN**  
CH-1211 Geneva 23  
Switzerland



the  
**Large  
Hadron  
Collider**  
project

LHC Project Document No.

**LHC-B-ES-0004 rev 2.0**

CERN Div./Group or Supplier/Contractor Document No.

**SL-BI**

EDMS Document No.


**328136**

Date: 2004-02-13

## Functional Specification

### **ON THE MEASUREMENT OF THE TUNES, COUPLING & DETUNINGS WITH MOMENTUM AND AMPLITUDE IN LHC**





# Scope, Boundaries, Responsibilities...


## *LARP*

CERN provides all hardware for LHC

- kicker amplifiers, kickers, and pickups
- Direct Diode Detection AFEs
- Digitizer boards
- DAB64 Boards - FPGA for processing plus VME interface
  - LHC (BPM, BLM, BCM,...) and LARP (PLL, Lumi, Schottky) standard
- VME crates and crate computers for CERN installation

LARP provides all software up to LHC Control System

- VME crates and crate computers for LHC test installation at BNL
- gate array programming
- FEC programming
- LabVIEW control program, collaboration on LHC equivalent (FESA)
- specification and testing of LHC TF Applications software
- testing at RHIC, with and without beam
- pre-beam and beam commissioning support at LHC



**LARP**

# Tune Feedback Planning

## **FY06**


- Demonstrate functioning system on RHIC run
- Develop electronics and firmware to support RHIC and SPS runs
- Complete system development in RHIC
- Deliver and test a system for CERN SPS run
- Final Design review

## **FY07**


- All 4 planes ready for LHC commissioning
- All firmware and software ready for beam commissioning
- Support installation and hardware commissioning
- Support beam commissioning



# LHC DAQ Interface - DABIV Board



J. Gonzales, CERN



**LARP**

# LARP DAQ Workshop

Attended by representatives of all labs


April 25, 2006

Daryl Bisop (TRUIMF), designer of the DAB board, gave a comprehensive description of the board design and its firmware programming

Rhodri Jones did a live demonstration of the hardware functionality at LBL

Used signal from pulse generator, processed by LUMI analog shaper

Round table discussion on how to implement system at LARP labs



## DAQ software/firmware for LARP instruments

### *LARP*

Real Time OS problem to compile LynxOS at US labs

- This stalled our efforts for months

- Licensing problem

LabView proposed by CERN

- Use VME-USB bridge card

LARP labs can develop expert Vis in LabView and deliver to CERN

- Uses the bridge card in the US


CERN implements the FESA interface, provides LabView connection

Expert panels available through CERN's FESA

LARP labs provide functional specification of memory interface

CERN develops GUIs for device controls

- Both expert and operator



**LARP**

## Open Issue/Opportunity

LHC@FNAL opens the door to experiments or observations  
at LHC directly from LARP sites

FNAL is leading the way

Ideal for 'passive' devices

I.e. Schottky monitor, luminosity monitor


Could make present effort on Schottky more effective

Not clear how much will be available by commissioning

CERN controls must be deeply involved for this to happen

Priorities may not be aligned

CERN is now looking at ways to facilitate



**LARP**

## Common Instrumentation Plans


Commissioning teams created at CERN, LARP plans to provide instrumentation commissioning support

New task proposals have been presented in a common session

- AC dipole

- Synchrotron light based diagnostics

Instrumentation group will do its assessment with CERN input



# LARP Instrumentation Integration Plan


## *LARP*

Planned documentation for each instrument

1. FS - Roles and Responsibilities  
Defines who does what, when
2. ES- Technical Specification  
Complete description of the device, its interfaces, its requirements....
3. ES - Functional Spec (of DAB 64x interface)  
Definition of what functions and features are included in the data acquisition system
4. ES - Memory Map of Firmware  
How the data is transferred to the control system
5. Any other document  
(ES) Safety, installation, HW checkout and commissioning,
6. FS - Acceptance Plan and signoff list  
Contains a list of deliverables from LARP to CERN  
Signoff list  
Once accepted, defines the end point of LARP's contribution to the instrument

FS= Functional Specification ES=Engineering Specification





**LARP**

# Implementation


The above docs have approvals on both sides

CERN and LARP

PIs are the single points of contact at each side of the ocean

Documents reside in EDMS and in LARP's databases

We aim to have the first two and the last one ready for the  
DoE review in June



***LARP***

## New Tasks

Several new tasks are emerging

- AC Dipole


- Synchrotron light based diagnostics

Being considered with other AS new proposals

As the existing tasks come to an end, funds will become available for new proposals

Instruments are chosen in close collaboration with CERN


- Current devices were not part of baseline design of LHC



**LARP**

## Conclusions - Challenges

- Funding
  - We are working with LARP management to continue securing adequate funding
  - With LHC commissioning approaching, we cannot tolerate schedule slips
- LARP task sheets continue to define scope and budget year by year
- Funding requests are also managed through task sheets
  - Detail 'project' reviews validate overall cost and schedule
- Integration with beam commissioning activities is essential to the survival of the instruments provided by the LARP collaboration and LARP is planning accordingly



**LARP**

## Summary

- LARP Instrumentation will build, commission, and integrate into LHC operations advanced instrumentation and diagnostics for helping LHC
  - reach design energy
  - reach design luminosity
- **Strong collaborative efforts are in place and evolving**
  - Tune feedback is fully leveraging RHIC experience and includes CERN staff
  - Lumi plans to do the same with RHIC run 6
  - Schottky's experience at FNAL is a great asset
    - synergies with BNL are fully leveraged
  - US colliders are an essential test bed for system development
- This program will advance the US HEP program by
  - Enhancing US accelerator skills
  - Developing advanced diagnostic techniques that will apply to present and future US programs
  - Help maximize LHC performance

