

*If you are using a printed copy of this procedure, and not the on-screen version, then you **MUST** make sure the dates at the bottom of the printed copy and the on-screen version match. The on-screen version of the Collider-Accelerator Department Procedure is the Official Version. Hard copies of all signed, official, C-A Operating Procedures are kept on file in the C-A ESHQ Training Office, Bldg. 911A.*

C-A OPERATIONS PROCEDURES MANUAL

ATTACHMENT

4.56.aq RHIC Zone 7z1 Sweep Checklist

Text Pages 2 through 3

C-A OPM Procedures in which this Attachment is used.

4.56		

Hand Processed Changes

<u>HPC No.</u>	<u>Date</u>	<u>Page Nos.</u>	<u>Initials</u>
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

Approved: *Signature on File*
 Collider-Accelerator Department Chairman Date

P. Ingrassia, W. MacKay

RHIC Zone 7z1 Sweep Checklist

Team Leader (TL) _____ Sweeper#2 (S2) _____



Time: _____ Date: _____

Warning:

IF any workers are encountered during the sweep, **THEN** contact the OC to see if the sweep should be aborted. Workers shall leave the enclosure **WITH** the sweep team. **IF** the workers crash out of the enclosure **AND** do not exit with the sweep team, **THEN** the sweep shall be re-started.

Prerequisites

- Two persons to perform the sweep,
- At least one sweeper not restricted from working at heights over five feet.
- RHIC Zone 7z1 Sweep Checklist (two pages)
- Required Tools: at least one flashlight,
- **Walkie-talkies (no phones at 7GE1)**
- Approved padlocks (2) for 7MD1 gate and Vapor Barrier Gate
- All Doors closed THEN 7z1 set to Controlled Access
- Keys: Sweep Reset key S/R015, Controlled Access key CA014, padlock key (RG184), padlock key (245341)



Note:

References to positions in the tunnel are made using the RHIC magnets. The identity of the local magnet can be determined by looking up at the "lower" cable tray and reading the magnet name on a blue (B) or yellow (Y) label. For example, the convention used is: I05Q17 (Inside, Q17) or O-05Q17 (Outside, Q17). References are for inside locations and are visible only by the TL

check

1. Sweep team goes to gate 7GE1 TL requests simultaneous release from MCR.
2. TL opens 7GE1 gate by turning the CA014 key clockwise, in the Controlled Access key-switch while Operator in MCR presses simultaneous release for 7GE1.

CONTINUED ON REVERSE SIDE

- ___ 3. Before start of sweep walk CW to 7MD1 where TL verifies 7MD1 gate is padlocked and reset. IF the gate is not padlocked then sweep the area, padlock the door, and reset the gate.
- ___ 4. Sweep Team walks to 7GS1 doors. (TL inside and Sweeper 2 outside).
- ___ 5. TL resets 7GS1 gate by turning S/R015 key in the RESET keyswitch at 7GS1-I
- ___ 6. TL observes RESET lamp light
- ___ 7. TL STARTS SWEEP by turning the S/R015 key CW in the SWEEP key-switch on 7CS1.
- ___ 6. TL observes AREA SECURED lamp blink once.
- ___ 7. Sweep team sweeps Clockwise (CW) around RHIC.
- ___ 9. TL stops to check the Exhaust Fan Vent Barrier at I-07Q17.
- ___ 10. Sweep team sweeps Clockwise (CW) around RHIC.
- ___ 11. S2 stands static watch at the electrical services alcove opposite I07Q13.
- ___ 12. TL enters the alcove and goes to the ladder at 7EL1.
- ___ 13. IF there is no mirror to verify no one is on the landing at the top of the ladder, THEN TL must climb the ladder to verify no one is on the landing and to check that 7EL1 is closed.
- ___ 14. TL resets gate 7EL1 using the S/R015 key in the Reset keyswitch at the bottom of the ladder.
- ___ 15. IF 7EL1 will not reset THEN TL climbs the ladder, closes 7EL1, then repeats step 14.
- ___ 16. TL observes RESET lamp lights after RESET.
- ___ 17. TL sets second check station (7CS2) by turning S/R015 key in the SWEEP keyswitch.
- ___ 18. TL observes AREA SECURED lamp blink once.
- ___ 19. TL searches goes to the far corner of the alcove to 7CS3.
- ___ 20. TL sets third check station (7CS3) by turning S/R015 key in the SWEEP keyswitch.
- ___ 21. TL observes AREA SECURED lamp blink once.
- ___ 22. TL checks inside EVERY rack and then sweeps out the alcove and joins S2.
- ___ 23. TL checks fan vent barrier on vent above S2 and observes overhead barricade is in place.
- ___ 24. Sweep team sweeps Clockwise (CW) around RHIC.
- ___ 25. Sweep Team stops to check the inner and outer Exhaust Fan Vent Barriers at I07Q9.
- ___ 26. Sweep team sweeps Clockwise (CW) around RHIC.
- ___ 27. Sweep Team stops to check the Electrical Alcoves and overhead barricades at I07D5
- ___ 28. Sweep team sweeps Clockwise (CW) around RHIC to I07Q3 before the Muon Steel.
- ___ 29. TL stands static watch at I07Q3
- ___ 30. S2 checks exhaust fan vent grating at O-07Q3.
- ___ 31. Sweeper # 2 walks to Muon Steel and sweeps back to the stairs.
- ___ 32. S2 checks exhaust fan vent grating at O-07Q1.
- ___ 33. S2 goes down the stairs, walks to the Muon steel and searches the gap between the steel and the tunnel with a flashlight.
- ___ 34. S2 sweeps the mezzanine, climbs the stairs.
- ___ 35. S2 goes to the caged area at the end of the Dx magnet and sweeps the caged area from the outside of the cage. IF the door is unlocked then they will go in, sweep the cage, exit, and padlock the door.
- ___ 36. S2 sweeps to I07Q3 and joins TL
- ___ 37. S2 stands static watch (at I07Q3) where they can see the entry to the stairs on the opposite side of the tunnel.
- ___ 38. TL walks to Muon Steel, unlocks padlock, opens the Vapor Barrier Gate, searches the barricaded volume beyond the Vapor Barrier Gate, closes and padlocks the Vapor Barrier gate, and sweeps back to the stairs.
- ___ 39. TL goes down the stairs, walks to the Muon steel and searches the gap between the steel and the tunnel with a flashlight.
- ___ 40. TL sweeps the mezzanine, but DOES NOT climb the stairs.
- ___ 41. TL CALLS to S2 to join him/her.
- ___ 42. Sweep Team sweeps out labyrinth to 7GE1.
- ___ 43. TL ENDS SWEEP by turning the S/R015 key SWEEP key on 7CS4.
- ___ 44. TL observes the yellow AREA SECURED lamp is lighted
- ___ 45. TL radios MCR for simultaneous release for gate 7GE1.
- ___ 46. Sweep Team sweeps out 7z1 through 7GE1 door.
- ___ 47. TL contacts MCR and confirms that gates are reset and 7z1 zone indicates sweep is good.

Note:
IF the AREA SECURED lamp is not lit THEN contact MCR to verify sweep is good.

- ___ 48. Sweep and lock fenced area outside 7GE1. Lock with corbin padlock #245341 found on the gate.
- ___ 49. After returning keys to the keytree, TL resets 7GE1 using the RHIC PanelView
- ___ 50. After returning to MCR and verifying that all information is filled out completely, TL files the checklist in FY_xx Sweep Log binder.