Official copies of these procedures are maintained at this website.

Before using a printed copy, verify that it is the most current version by checking the document issue date on this website. Signed copies of these official procedures are maintained at the Training Office.

C-A OPERATIONS PROCEDURES MANUAL

| 7.1.23 Seal | Gas Com | pressor Start-Up |
|-------------|---------|------------------|
|-------------|---------|------------------|

Text Pages 2 through 3

Hand Processed Changes

| HPC No. | <u>Date</u> | Page Nos. | <u>Initials</u> | |
|---------|-------------|-----------------------------|-----------------|------|
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | Signature on File | | |
| | | Collider-Accelerator Depart | rtment Chairman | Date |

S. Sakry

7.1.23 Seal Gas Compressor Start-Up

1. Purpose

This procedure provides instructions for starting the seal gas compressor associated with the turbines on the RHIC 25 kW helium refrigerator located in the refrigeration wing of 1005R.

2. Responsibilities

- 2.1 The shift supervisor, or an operator designated by the shift supervisor, is responsible for conducting the procedure and providing documentation in the Cryogenic Control Room Log.
- 2.2 Should a problem arise in the process of starting the seal gas compressor, the shift supervisor shall report to the technical supervisor for instructions before continuing.

3. <u>Prerequisites</u>

3.1 Main cooling water system operating (cooling towers).

4. Precautions

4.1 If there is liquid helium in the refrigerator pots, all personnel entering the refrigeration wing of 1005R must have a Personal Oxygen Monitor (POM) and carry an emergency escape pack.

5. <u>Procedure</u>

| 1. | Ensure oil level is visible in the upper sight glass. |
|----|--|
| 2. | Ensure open control air supply valve. Valve is located on maniford mounted to Adsorber 'A' (upper level). |
| 3. | Ensure circuit breaker #1 of the Main Distribution Panel is in the 'On' position and the associated fused disconnect is closed. Both items are located on the lower level south wall across from the compressor. |
| 4. | Ensure closed the 1" and 1 ½" manual bypass valves. |
| 5. | Open the manual discharge valve. |
| 6. | Ensure open the low pressure surge tank inlet valve (located next to seal gas compressor). |

| | _ 7. | Ensure open the seal gas compressor discharge to main compressor valve. Valve is located on ceiling of lower level near Vacuum System#1. | |
|--------------|--|---|--|
| | _ 8. | Ensure open the seal gas compressor make-up valve from pure helium gas. Valve s located on the column between Adsorbers 'A' and 'B' on the lower level. | |
| | _ 9. | Open coolant water return valve W942M and supply valve W941M (water supply and return to Rotoflow oil skid #1 must also be open to provide a path). | |
| | _ 10. | On the seal gas control panel, place the Local/Remote switch in Remote. | |
| | _ 11. | Reset any local alarms on the compressor control panel. | |
| | _ 12. | Ensure open the high pressure surge tank isolation valve (located on tank outside of west end of refrigerator room). | |
| | _ 13. | On CRISP control page D69, click on "Start Compressor". The seal gas compressor should start, load and switch bypass valve H1258 and discharge valve H1252 to automatic mode. | |
| <u>Docum</u> | <u>ientati</u> | <u>on</u> | |
| 6.1 | The check off lines on the procedure are for place keeping only. The procedure is not to be initialed or signed, it is not a record. | | |
| 6.2 | The shift supervisor shall document the completion of the procedure in the Cryogenics Control Room Log. | | |
| Refere | ences | | |
| None | | | |
| Attach | <u>ments</u> | | |
| None | | | |

6.

7.

8.