Official copies of these procedures are maintained at this website.

Before using a printed copy, verify that it is the most current version by checking the document issue date on this website. Signed copies of these official procedures are maintained at the Training Office.

C-A OPERATIONS PROCEDURES MANUAL

ATTACHMENT

9.5.5.b Examples Of Specific ALARA Work Practices

C-	A OPM Procedures in	which this Attachment	is used.	
	9.5.5			
	Hand Pro	cessed Changes		
HPC No.	<u>Date</u>	Page Nos.	<u>Initials</u>	
		_Signature On File		
	Co	llider-Accelerator Depar	rtment Chairman	Date

C. Schaefer

EXAMPLES OF SPECIFIC ALARA WORK PRACTICES

schedule work for longest cool down time (time since beam off)

keep a history of equipment malfunction

install quick-disconnects on vacuum system and magnet, water, and power cables

use radiation-hardened beam-line components

establish guidelines for area access based on radiation level

train on mock-up equipment prior to performing the work

design shielding for quick removal

use remote areas for storage of heavily irradiated equipment

assess personnel exposure data prior to work

reduce the density of beam-line components to reduce serviceability problems

use a sufficient number of radiation monitoring points in the pre-job radiation survey

select a trained and experienced work force

identify and coordinate resource requirements

perform ALARA pre-job review

plan access to and exit from the work area

provide for service lines (air, welding, ventilation)

provide communication

remove or shield sources of radiation

install temporary shielding

decontaminate

work in lowest radiation levels

perform as much work as practicable outside radiation areas

state requirements for tools

state staging requirements for materials, parts and tools

incorporate radiological control hold points

minimize discomfort of workers

inspect shielding after installation

conduct periodic radiation surveys during work

compare exposure received during installation of temporary shielding versus exposure

saved by not installing temporary shielding

shield travel routes

shield components with abnormally high radiation levels

shield position occupied by worker

keep excess personnel out of radiation area

workers assist in RWP preparation

evaluate use of fewer workers